



## **ADVERTISEMENT FOR BID FOR FURNISHING PER LINEAL FOOT PRICE FOR CAST IN PLACE PIPE WORK IN THE CITY OF WASHINGTON, IL**

The City of Washington, Illinois, will receive sealed bids for furnishing per lineal foot price for CAST IN PLACE PIPING work until **11:00 a.m. on Tuesday February 6<sup>th</sup>, 2024**, at City Hall, 301 Walnut Street, Washington IL 61571 at which time and place all bids will be publicly opened and read aloud.

Award of bid is anticipated to be on **Monday, March 4<sup>th</sup>, 2024**.

Specifications, Contract Documents, and Proposal Forms for the Public Works s Bid Document **No. PW-24-08** are on file in and may be obtained from the Office of the Public Works Director at the above address.

The City of Washington, Illinois, reserves the right to reject any or all bids and waive any informality in bidding.

January 23<sup>th</sup>, 2024

Date of Publication

Valerie Brod

City Clerk  
City of Washington



**SPECIFICATIONS AND CONTRACT DOCUMENTS NO. PW-24-08**

**FOR FURNISHING CAST IN PLACE PIPING**

**TO THE CITY OF WASHINGTON, ILLINOIS**

**BID OPENING: Tuesday, February 6<sup>th</sup>, 2024 at 11:00 a.m.**

**BID DEPOSIT: Not Required**

**PERFORMANCE BOND: Not Required**

**REQUIRED FOR USE BY THE**

**CITY OF WASHINGTON PUBLIC WORKS DEPARTMENT**

# **SPECIAL CONDITIONS**

## **Term of Contract**

This Contract shall take effect May 1, 2024, and expire on April 30, 2025.

## **SPECIFICATIONS FOR CURED-IN-PLACE PIPE (CIPP) (As Provided by Insituform)**

### **1. INTENT**

**1.1** It is the intent of this specification to provide for the reconstruction of pipelines and conduits by the installation of a resin-impregnated flexible tube, which is tightly formed to the original conduit. The resin is cured using either hot water under hydrostatic pressure or steam pressure within the tube. The Cured-In-Place Pipe (CIPP) will be continuous and tight fitting. The work shall be completed within ( ) calendar days from the "Notice to Proceed".

### **2. REFERENCED DOCUMENTS**

**2.1** This specification references standards from the American Society for Testing and Materials, such as: ASTM F1216 (Rehabilitation of Existing Pipelines and Conduits by the Inversion and Curing of a Resin-Impregnated Tube), ASTM F1743 (Rehabilitation of Existing Pipelines and Conduits by Pulled-in-Place Installation of Cured-in-Place Thermosetting Resin Pipe (CIPP)), ASTM D5813 (Cured-in-Place Thermosetting Resin Sewer Pipe), ASTM D790 (Test Methods for Flexural Properties of Un-reinforced and Reinforced Plastics and Electrical Insulating Materials), and D2990 (Tensile, Compressive, and Flexural Creep and Creep-Rupture of Plastics) which are made a part hereof by such reference and shall be the latest edition and revision thereof. In case of conflicting requirements between this specification and these referenced documents, this specification will govern.

### **3. PRODUCT, MANUFACTURER/INSTALLER QUALIFICATION REQUIREMENTS**

**3.1** Since sewer products are intended to have a 50-year design life, and in order to minimize the Owner's risk, only proven products with substantial successful long-term track records will be approved. All trenchless rehabilitation products and installers must be pre-approved prior to the formal opening of proposals. Products and Installers seeking approval must meet all of the following criteria to be deemed Commercially Acceptable:

**3.1.1** For a Product to be considered Commercially Proven, a minimum of five successful wastewater collection system projects of a similar size and scope of work shall be performed in the U.S. and documented to the satisfaction of the Owner to assure commercial viability

**3.1.2** For an Installer to be considered as Commercially Proven, the Installer must satisfy all insurance, financial, and bonding requirements of the Owner, and must have had at least 5 (five) years active experience in the commercial installation. In addition, the Installer must have successfully installed at least 1,000,000 feet of a cured-in-place product in wastewater collection systems. Acceptable documentation of these minimum installations must be submitted to the Owner.

Installer's project managers must have a minimum of 2 years of CIPP installation experience and must be on-site during the installation of the CIPP products.

**3.1.3** Sewer rehabilitation products submitted for approval must provide third party test results supporting the structural performance (short-term and long-term) of the product and such data shall be satisfactory to the Owner. No product will be approved without independent third-party testing verification.

**3.1.4** Both the rehabilitation manufacturing and installation processes shall operate under a quality management system which is third-party certified to ISO 9000 or other recognized organization standards. Proof of certification shall be required for approval.

**3.1.5** Proposals must be labeled clearly on the outside of the proposal envelope, listing the product name and installer being proposed. Only proposals using pre-approved products and installers will be opened and read. Proposals submitted on products and/or from installers that have not been pre-approved will be returned unopened

**3.1.6** The owner authorizes the use of proven materials that serve to enhance the pipe performance specified herein. Proven materials have passed independent laboratory testing, not excluding long-term (10,000 hour) structural behavior testing, and have been successfully installed to repair failing host pipes in the U. S. for at least 4 years. In addition to the aforementioned, the owner requires that the contractor demonstrate that the enhancements proposed exceed the specifications herein, prior to the installation of the enhanced material systems. This section in no way shall be interpreted as authorization to deviate from the minimum standard practices set forth herein. Documentation for products and installers seeking pre-approved status must be submitted no less than two weeks prior to proposal due date to allow time for adequate consideration. The Owner will advise of acceptance or rejection a minimum of three days prior to the due date. All required submittals must be satisfactory to the Owner.

#### **4. MATERIALS**

**4.1** Tube - The sewn Tube shall consist of one or more layers of absorbent non-woven felt fabric and meet the requirements of ASTM F1216, Section 5.1 or ASTM F1743, Section 5.2.1 or ASTM D 5813, Sections 5 and 6. The tube shall be constructed to withstand installation pressures, have sufficient strength to bridge missing pipe, and stretch to fit irregular pipe sections.

**4.1.1** The wet-out Tube shall have a relatively uniform thickness that when compressed at installation pressures will equal or exceed the calculated minimum design CIPP wall thickness. 3

**4.1.2** The Tube shall be manufactured to a size that when installed will tightly fit the internal circumference and length of the original pipe. Allowance should be made for circumferential stretching during installation.

**4.1.3** The outside layer of the Tube shall be coated with an impermeable, flexible membrane that will contain the resin and allow the resin impregnation (wet out) procedure to be monitored.

**4.1.4** The Tube shall contain no intermediate or encapsulated elastomeric layers. No material shall be included in the Tube that may cause delamination in the cured CIPP. No dry or unsaturated layers shall be evident.

**4.1.5** The wall color of the interior pipe surface of CIPP after installation shall be a relatively light reflective color so that a clear detailed examination with closed circuit television inspection equipment may be made.

**4.1.6** Seams in the Tube shall be stronger than the non-seamed felt material.

**4.1.7** The Tube shall be marked for distance at regular intervals along its entire length, not to exceed 5 ft. Such markings shall include the Manufacturers name or identifying symbol. The tubes must be manufactured in the USA.

**4.2** Resin - The resin system shall be a corrosion resistant polyester or vinyl ester system including all required catalysts, initiators that when cured within the tube create a composite that satisfies the requirements of ASTM F1216, ASTM D5813 and ASTM F1743, the physical properties herein, and those which are to be utilized in the submitted and approved design of the CIPP for this project. The resin shall produce a CIPP that will comply with the structural and chemical resistance requirements of this specification.

## **5. STRUCTURAL REQUIREMENTS**

**5.1** The CIPP shall be designed as per ASTM F1216, Appendix X.1. The CIPP design shall assume no bonding to the original pipe wall.

**5.2** The Contractor must have performed long-term testing for flexural creep of the CIPP pipe material installed by his Company. Such testing results are to be used to determine the long-term, time dependent flexural modulus to be utilized in the product design. This is a performance test of the materials (Tube and Resin) and general workmanship of the installation and curing as defined within the relevant ASTM standard. A percentage of the instantaneous flexural modulus value (as measured by ASTM D790 testing) will be used in design calculations for external buckling. The percentage, or the long-term creep retention value utilized, will be verified by this testing. Retention values exceeding 50% of the short-term test results shall not be applied unless substantiated by qualified third-party test data to the Owner's satisfaction. The materials utilized for the contracted project shall be of a quality equal to or better than the materials used in the long-term test with respect to the initial flexural modulus used in the CIPP design.

**5.3** The Enhancement Factor 'K' to be used in 'Partially Deteriorated' Design conditions shall be assigned a value of 7.4

**5.4** The layers of the cured CIPP shall be uniformly bonded. It shall not be possible to separate any two layers with a probe or point of a knife blade so that the layers separate cleanly or the probe or knife blade moves freely between the layers. If the layers separate during field sample testing, new samples will be required to be obtained from the installed pipe. Any reoccurrence may cause rejection of the work.

**5.5** The cured pipe material (CIPP) shall conform to the structural properties, as listed below.

**MINIMUM CIPP PHYSICAL PROPERTIES** Cured Polyester Composite Property Test Method min. per ASTM F1216 Enhanced Resin Modulus of Elasticity ASTM D790 250,000 psi 400,000 psi Flexural Stress ASTM D790 4,500 psi 4,500 psi

**5.6** The required structural CIPP wall thickness shall be based as a minimum, on the physical properties in Section 5.5 or greater values if substantiated by independent lab testing and in accordance with the design equations in the Appendix X1. Design Considerations of ASTM F1216, and the following design parameters: Design Safety Factor (typically used value) = 2.0 Retention Factor for Long-Term Flexural Modulus to be used in Design = 50% - 75% (As determined by long-term tests described in section 5.2 and approved by the Owner) Ovality\* (calculated from (X1.1of ASTM F1216) = % Enhancement Factor, K = See Section 5.3 Groundwater Depth (above invert of existing pipe)\* = ft. Soil Depth (above crown of existing pipe)\* = ft. Soil Modulus\*\* = psi Soil Density\*\* = pcf Live Load\*\* = H20 Highway Design Condition (partially or fully deteriorated)\*\*\* = \*\*\* \* Denotes information, which can be

provided here or in inspection videotapes or project construction plans. Multiple line segments may require a table of values. \*\* Denotes information required only for fully deteriorated design conditions. \*\*\* Based on review of video logs, conditions of pipeline can be fully or partially deteriorated. (See ASTM F1216 Appendix) The Owner will be sole judge as to pipe conditions and parameters utilized in design.

**5.7** Any layers of the tube that are not saturated with resin prior to insertion into the existing pipe shall not be included in the structural CIPP wall thickness computation.

## **6. TESTING REQUIREMENTS**

**6.1** Chemical Resistance - The CIPP shall meet the chemical resistance requirements of ASTM F1216, Appendix X2. CIPP samples for testing shall be of tube and resin system similar to that proposed for actual construction. It is required that CIPP samples with and without plastic coating meet these chemical-testing requirements.

**6.2** Hydraulic Capacity - Overall, the hydraulic cross-section shall be maintained as large as possible. The CIPP shall have a minimum of the full flow capacity of the original pipe before rehabilitation. Calculated capacities may be derived using a commonly accepted roughness coefficient for the existing pipe material taking into consideration its age and condition.

**6.3** CIPP Field Samples - When requested by the Owner, the Contractor shall submit test results from field installations of the same resin system and tube materials as proposed for the actual installation. These test results must verify that the CIPP physical properties specified in Section 5.5 have been achieved in previous field applications. Samples for this project shall be made and tested as described in Section 10.1.

## **7. INSTALLATION RESPONSIBILITIES FOR INCIDENTAL ITEMS**

**7.1** It shall be the responsibility of the Owner to locate and designate all manhole access points open and accessible for the work, and provide rights-of-access to these locations. If a street must be closed to traffic because of the orientation of the sewer, the Owner shall institute the actions necessary to provide access during this for the mutually agreed time period. The Owner shall also provide free access to water hydrants for cleaning, installation and other process related work items requiring water.

**7.2** Cleaning of Sewer Lines - The Contractor, when required, shall remove all internal debris out of the sewer line that will interfere with the installation of CIPP. The Owner shall also provide a dumpsite for all debris removed from the sewers during the cleaning operation. Unless stated otherwise, it is assumed this site will be at or near the sewage treatment facility to which the debris would have arrived in absence of the cleaning operation. Any hazardous waste material encountered during this project will be considered as a changed condition.

**7.3** Bypassing Sewage - The Contractor, when required, shall provide for the flow of sewage around the section or sections of pipe designated for repair. Plugging the line at an existing upstream manhole and pumping the flow into a downstream manhole or adjacent system shall make the bypass. The pump(s) and bypass line(s) shall be of adequate capacity to accommodate the sewage flow. The Owner may require a detail of the bypass plan to be submitted.

**7.4** Inspection of Pipelines - Inspection of pipelines shall be performed by experienced personnel trained in locating breaks, obstacles and service connections using close circuit television (CCTV) inspection techniques. The pipeline interior shall be carefully inspected

to determine the location of any conditions that may prevent proper installation of CIPP. These shall be noted and corrected. A videotape and suitable written log for each line section shall be produced for later reference by the Owner.

**7.5 Line Obstructions** - It shall be the responsibility of the Contractor to clear the line of obstructions such as solids and roots that will prevent the insertion of CIPP. If pre-installation inspection reveals an obstruction such as a protruding service connection, dropped joint, or a collapse that will prevent the installation process, that was not evident on the pre-bid video and it cannot be removed by conventional sewer cleaning equipment, then the Contractor shall make a point repair excavation to uncover and remove or repair the obstruction. Such excavation shall be approved in writing by the Owner's representative prior to the commencement of the work and shall be considered as a separate pay item.

**7.6 Public Notification** - The Contractor shall make every effort to maintain sewer service usage throughout the duration of the project. In the event that a connection will be out of service, the longest period of no service shall be 8 hours. A public notification program shall be implemented, and shall as a minimum, require the Contractor to be responsible for contacting each home or business connected to the sanitary sewer and informing them of the work to be conducted, and when the sewer will be off-line. The Contractor shall also provide the following: A. Written notice to be delivered to each home or business the day prior to the beginning of work being conducted on the section, and a local telephone number of the Contractor they can call to discuss the project or any potential problems. B. Personal contact with any home or business, which cannot be reconnected within the time stated in the written notice.

**7.7** The Contractor shall be responsible for confirming the locations of all branch service connections prior to installing the CIPP.

## **8. INSTALLATION**

**8.1** CIPP installation shall be in accordance with ASTM F1216, Section 7, or ASTM F1743, Section 6, with the following modifications:

**8.1.1 Resin Impregnation** - The quantity of resin used for tube impregnation shall be sufficient to fill the volume of air voids in the tube with additional allowances for polymerization shrinkage and the potential loss of resin during installation through cracks and irregularities in the original pipe wall, as applicable.

**8.1.2 Tube Insertion** – The wet out tube shall be positioned in the pipeline using either inversion or a pull-in method as defined within relevant ASTM standards previously stipulated. If pulled into place, a power winch or its equivalent should be utilized and care should be exercised not to damage the tube as a result of pull-in friction. The tube should be pulled-in or inverted through an existing manhole or approved access point and fully extend to the next designated manhole or termination point.

**8.1.3 Temperature gauges** shall be placed between the tube and the host pipe's invert position to monitor the temperatures during the cure cycle. 7

**8.1.4 Curing** shall be accomplished by utilizing hot water under hydrostatic pressure or steam pressure in accordance with the manufacturer's recommended cure schedule. A cool-down process shall be conducted that complies with the resin manufacturer's specification.

## **9. REINSTATEMENT OF BRANCH CONNECTIONS**

**9.1** It is the intent of these specifications that branch connections to buildings be re-opened without excavation, utilizing a remotely controlled cutting device, monitored by a CCTV. The Contractor shall certify a minimum of two complete functional cutters plus key spare components are on the job site before each installation or are in the immediate area of the jobsite and can be quickly obtained. Unless otherwise directed by the Owner or his authorized representative, all laterals will be reinstated. No additional payment will be made for excavations for the purpose of reopening connections and the Contractor will be responsible for all costs and liability associated with such excavation and restoration work.

## **10. INSPECTION**

**10.1** CIPP samples shall be prepared for each installation designated by the owner/engineer or approximately 20% of the project's installations. Pipe physical properties will be tested in accordance with ASTM F1216 or ASTM F1743, Section 8, using either method proposed. The flexural properties must meet or exceed the values listed on page SC3 and SC4 of this specification, Table 1 of ASTM F1216 or the values submitted to the Owner/engineer by the contractor for this project's CIPP wall design, whichever is greater.

**10.2** Wall thickness of samples shall be determined as described in paragraph 8.1.6 of ASTM F1743. The minimum wall thickness at any point shall not be less than 87½% of the submitted minimum design wall thickness as calculated in paragraph 5.6 of this document.

**10.3** Visual inspection of the CIPP shall be in accordance with ASTM F1743, Section 8.6.

## **11. CLEAN-UP**

**11.1** Upon acceptance of the installation work and testing, the Contractor shall restore the project area affected by the operations to a condition at least equal to that existing prior to the work.

## **12. PAYMENT**

**12.1** Payment for the work included in this section will be in accordance with the prices set forth in the proposal for the quantity of work performed. Progress payments will be made monthly based on the work performed during that period.

## **13. QUANTITIES**

The quantities shown herein are estimated for canvassing purposes only, and as such may not represent the actual quantities required during the term of any contract made pursuant to these specifications. Nothing contained herein shall be construed as an obligation of the City of Washington to order or pay for any quantity of material other than that amount determined to meet the actual requirements of the City. The right is reserved to increase or decrease the quantities shown herein at any time during the life of the contract. The City will be obligated to pay for only the actual quantities ordered and received.



#### **14. BASIS OF AWARD**

Bids will be canvassed on the basis of the unit prices as shown on Page P-1 of the Proposal. Unit prices shown on the proposal shall include **all** delivery charges for the quantities shown. The City reserves the right to waive technicalities or to reject any and all bids when, in the opinion of the City Council, the best interests of the City of Washington will be served by such action.

#### **15. ORDERING AND DELIVERY**

Orders shall be placed by telephone direct to the Contractor by personnel of the City of Washington, Department of Public Works. A list of authorized personnel will be furnished to the Contractor upon request.

The Contractor will furnish and deliver to the job site the ordered quantities no later than 30 day after placement of the order.

#### **16. TESTING**

The City reserves the right to require a statement from the manufacturer that the CIPP has been inspected and tested and conforms to the Specifications. The contractor shall provide copies of performance tests and field data reports upon request by the City for purposes of verifying conformance to the specifications.

#### **17. BILLING**

All invoices for accepted quantities should be sent daily to the City of Washington, 301 Walnut Street, Washington, Illinois 61571. All invoices must clearly show the description, quantity received, unit price, and the City's Purchase Order number.

#### **18. PRICE ESCALATION**

The prices quoted herein shall remain firm for the contract period.

#### **19. CERTIFICATION OF COMPLIANCE**

In accordance with Article 33E of the Criminal Code of 1961, as amended, the bidder is required to fill out and submit with his proposal the Certification of Compliance included with this bid document.

#### **20. EXCEPTIONS TO SPECIFICATIONS**

Any exceptions to these specifications shall be clearly explained on a separate page by the bidder on his firm's letterhead, to be attached to and submitted with these documents prior to or at the time of bid opening. Should a bidder submit a proposal without a separate statement of exception, it shall be assumed the proposal is in full compliance with these specifications.

## **21. CORRECTIONS**

All prices and notations must be typed in or written in ink.

## CERTIFICATION OF COMPLIANCE

The undersigned, being first duly sworn on oath, deposes and states that he has the authority to make this certification on behalf of the bidder.

\_\_\_\_\_  
(Name of Company)

- (a) That in connection with this procurement,
  - (1) the prices in this bid have been arrived at independently, without consultation, communication, or agreement, for the purpose or restricting competition, as to any matter relating to such prices with any other bidder or with any competitor;
  - (2) the prices which have been quoted in this bid have not been knowingly disclosed by the bidder and will not be knowingly disclosed by the bidder prior to opening directly or indirectly to any other bidder or to any competitor; and
  - (3) no attempt has been made or will be made by the bidder to induce any other person or firm to submit or not to submit a bid for the purpose of restricting competition.
  
- (b) The undersigned further states
  - (1) he is the person in the bidder's organization responsible within that organization for the decision as to the prices being bid herein and that he has not participated, and will not participate, in any action contrary to (a)(1) through (a)(3) above; or
  - (2)(a) he is not the person in the bidder's organization responsible within that organization for the decision as to the prices being bid herein but that he has been authorized to act as agent for the persons responsible for such decision in certifying that such persons have not participated, and will not participate, in any action contrary to (a)(1) through (a)(3) above, and as their agent does hereby so certify; and (b) that he has not participated, and will not participate in, any action contrary to (a)(1) through (a)(3) above.
  
- (c) The undersigned certifies that the bidder is not barred from bidding on this contract as a result of a conviction for the violation of State laws prohibiting bid-rigging or bid-rotating.
  
- (d) It is expressly understood that the foregoing statements, representations, and promises are made as a condition to the right of the bidder to receive payment under any award made hereunder.

Authorized Signature: \_\_\_\_\_

Title: \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this

\_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

\_\_\_\_\_  
Notary Public

# PROPOSAL

The undersigned proposes, in accordance with the terms and conditions of the Contract Documents, of which this Proposal is a part, to furnish Cast in Place Piping to the City of Washington, Illinois, as described below, for the period beginning on May 1, 2024, and ending April 30, 2025, at the unit prices set forth below:

Quantity Delivered	6 Inch		8 Inch		10 Inch		12 Inch		15 Inch		18 Inch	
0 to 300 LF	\$		\$		\$		\$		\$		\$	
300 to 1,000 LF	\$		\$		\$		\$		\$		\$	
Over 1,000 LF	\$		\$		\$		\$		\$		\$	
End Seals	\$		\$		\$		\$		\$		\$	
Per Service Reconnect	\$		\$		\$		\$		\$		\$	

  

Quantity Delivered	21 Inch		24 Inch		27 Inch		32 Inch		36 Inch		42 Inch	
0 to 300 LF	\$		\$		\$		\$		\$		\$	
300 to 1,000 LF	\$		\$		\$		\$		\$		\$	
Over 1,000 LF	\$		\$		\$		\$		\$		\$	
End Seals	\$		\$		\$		\$		\$		\$	
Per Service Reconnect	\$		\$		\$		\$		\$		\$	

\* Special orders shall be on a "Cost Plus: basis, not to exceed 15% for the special material

Cash Billing Terms: \_\_\_\_\_

Person to Contact Regarding This Proposal: \_\_\_\_\_

Phone Number: \_\_\_\_\_

The undersigned also acknowledges having received a full set of the Contract Documents and Addenda Nos. \_\_\_\_ (None unless indicated).

Signature: \_\_\_\_\_

Name of Business: \_\_\_\_\_

Business Address: \_\_\_\_\_

\_\_\_\_\_

Business Phone: \_\_\_\_\_